

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
CARROLL COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Carroll County, Mississippi at the Carroll County Courthouse, Carrollton, Mississippi, until on the _____ day of _____, and shortly thereafter publicly opened for the construction of 0.109 miles of BOX CULVERT & APPROACHES on COUNTY ROAD 131 being known as Project No. LSBP-08(39) in Carroll County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE AT STA. 2+43	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	1,356.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	1,687.000	CY
CHANNEL EXCAVATION (FM)	120.000	CY
STRUCTURE EXCAVATION	148.000	CY
GRANULAR MATERIAL (LVM), (CLASS 4, GROUP "B")	521.000	CY
CLASS "B" STRUCTURAL CONCRETE	77.490	CY
REINFORCING STEEL	10,674.000	LB
24" REINFORCED CONCRETE PIPE, CLASS III	56.000	LF
36" REINFORCED CONCRETE PIPE, CLASS III	56.000	LF
24" REINFORCED CONCRETE PIPE, END SECTION	1.000	EA
36" REINFORCED CONCRETE PIPE, END SECTION	1.000	EA
24" BRANCH CONNECTION FOR REINFORCED CONCRETE PIPE TO WING_ WALL OF BOX	1.000	EA
36" BRANCH CONNECTION FOR REINFORCED CONCRETE PIPE TO WING WALL OF BOX	1.000	EA
RIGHT-OF-WAY MARKERS (TYPE II)	11.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	2.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	1.000	EA

SECTION 900
PROJECT NO. LSBP-08(39)
CARROLL COUNTY

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	3.520	TON
COMMERCIAL FERTILIZER (13:13:13)	1.760	TON
AMMONIUM NITRATE	0.180	TON
SEEDING	1.760	AC
VEGETATIVE MATERIALS FOR MULCH	5.280	TON
SOLID SODDING	412.000	SY
EXCELSIOR BLANKET	200.000	SY
TEMPORARY SILT FENCE	1,000.000	LF
LOOSE RIPRAP, 300 LB.	195.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V,	364.000	SY
AOS 0.21-0.43		
WATTLES, 12"	150.000	LF

NOTICE TO CONTRACTORS:

CONTRACT TIME: 90 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Carroll County, the LSBP Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Robert D. Willis, LSBP Engineer for Carroll County, Mississippi, P. O. Drawer 160, Grenada. The Cost is thirty five dollars (\$35.00) for plans and thirty five dollars (\$35.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Carroll County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Lloyd "honey" Ashmore, President
Carroll County Board of Supervisors