

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
PRENTISS COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Prentiss County, Mississippi at the Prentiss County Chancery Building, 201 West Commerce Street, Booneville, MS 38829, until 10:00 am on the 6th day of June, 2016 and shortly thereafter publicly opened for the construction of 0.071 miles of BRIDGE AND APPROACHES TO REPLACE BRIDGE NO. 108 on COUNTY ROAD 5091 being known as Project No. LSBP-59(24) in Prentiss County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF EXISTING BRIDGE @ STA. 16+54	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	405.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	15.000	CY
GRANULAR MATERIAL (LVM) (CLASS5, GROUP "B") (TYPE V) (AOS <0.43)	289.000	SY
RIGHT-OF-WAY MARKERS (TYPE I)	8.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4.000	EA
<u>EROSION CONTROL ITEMS:</u>		
AGRICULTURAL LIMESTONE	1.000	TON
COMMERCIAL FERTILIZER (13-13-13)	0.500	TON
AMMONIUM NITRATE	0.130	TON
SEEDING	0.500	AC
SOLID SODDING	100.000	SY
EXCELSIOR BLANKET	2,420.000	SY
TEMPORARY SILT FENCE (TYPE I OR II) (AOS 0.15-0.84)	600.000	LF
WATTLES, 20"	100.000	LF
<u>BRIDGE ITEMS:</u>		
TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
10" STEEL PILING	640.000	LF
BRIDGE CONCRETE, CLASS "B"	3.360	CY
REINFORCEMENT	64.000	LB

SECTION 900
PROJECT NO. LSBP-59(24)
PRENTISS COUNTY

19' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	12.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	6.000	EA
19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	4.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2.000	EA
PRECAST CONCRETE BARRIER RAIL	156.000	LF
31.33' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, STEEL PILE	2.000	EA
31' PRECAST CONCRETE CAP, END UNIT, STEELE PILE	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	46.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	85.000	SY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 60 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Prentiss County, the LSBP Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Kenneth P. Geno, Jr., LSBP Engineer for Prentiss County, Mississippi, P. O. Box 1526, Tupelo. The cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable Certified check or bid bond for five percent (5%) of the total bid, made payable to Prentiss County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Matt Murphy, President
Prentiss County Board of Supervisors

Publish: May 5th & May 12th, 2016